

---

This is an electronic reprint of the original article.  
This reprint may differ from the original in pagination and typographic detail.

Khalid Masood, Mustafa; Aikala, Antti; Seppänen, Olli; Singh, Vishal

## Multi-Building Extraction and Alignment for As-Built Point Clouds : A Case Study With Crane Cameras

*Published in:*  
Frontiers in Built Environment

*DOI:*  
[10.3389/fbuil.2020.581295](https://doi.org/10.3389/fbuil.2020.581295)

Published: 21/12/2020

*Document Version*  
Publisher's PDF, also known as Version of record

*Published under the following license:*  
CC BY

*Please cite the original version:*  
Khalid Masood, M., Aikala, A., Seppänen, O., & Singh, V. (2020). Multi-Building Extraction and Alignment for As-Built Point Clouds : A Case Study With Crane Cameras. *Frontiers in Built Environment*, 6, Article 581295.  
<https://doi.org/10.3389/fbuil.2020.581295>

---

This material is protected by copyright and other intellectual property rights, and duplication or sale of all or part of any of the repository collections is not permitted, except that material may be duplicated by you for your research use or educational purposes in electronic or print form. You must obtain permission for any other use. Electronic or print copies may not be offered, whether for sale or otherwise to anyone who is not an authorised user.



# Multi-Building Extraction and Alignment for As-Built Point Clouds: A Case Study With Crane Cameras

Mustafa K. Masood<sup>1\*</sup>, Antti Aikala<sup>1</sup>, Olli Seppänen<sup>1</sup> and Vishal Singh<sup>2</sup>

<sup>1</sup> Department of Civil Engineering, Aalto University, Espoo, Finland, <sup>2</sup> Centre for Product Design and Manufacturing (CPDM), Indian Institute of Science, Bengaluru, India

## OPEN ACCESS

### Edited by:

Kevin Han,  
North Carolina State University,  
United States

### Reviewed by:

Qian Wang,  
National University of Singapore,  
Singapore  
Uwe M. Stilla,  
Technical University of Munich (TUM),  
Germany  
Ali Khaloo,  
Cornell University, United States

### \*Correspondence:

Mustafa K. Masood  
mustafa.1.khalidmasood@aalto.fi

### Specialty section:

This article was submitted to  
Construction Management,  
a section of the journal  
Frontiers in Built Environment

**Received:** 08 July 2020

**Accepted:** 24 November 2020

**Published:** 21 December 2020

### Citation:

Masood MK, Aikala A, Seppänen O  
and Singh V (2020) Multi-Building  
Extraction and Alignment for As-Built  
Point Clouds: A Case Study With  
Crane Cameras.  
Front. Built Environ. 6:581295.  
doi: 10.3389/fbuilt.2020.581295

Automatic reality capture and monitoring of construction sites can reduce costs, accelerate timelines and improve quality in construction projects. Recently, automatic close-range capture of the state of large construction sites has become possible through crane and drone-mounted cameras, which results in sizeable, noisy, multi-building as-built point clouds. To infer construction progress from these point clouds, they must be aligned with the as-designed BIM model. Unlike the problem of aligning single buildings, the multi-building scenario is not well-studied. In this work, we address some unique issues that arise in the alignment of multi-building point clouds. Firstly, we show that a BIM-based 3D filter is a versatile tool that can be used at multiple stages of the alignment process. We use the building-pass filter to remove non-building noise and thus extract the buildings, delineate the boundaries of the building after the base is identified and as a post-processing step after the alignment is achieved. Secondly, in light of the sparseness of some buildings due to partial capture, we propose to use the best-captured building as a pivot to align the entire point cloud. We propose a fully automated three-step alignment process that leverages the simple geometry of the pivot building and aligns partial xy-projections, identifies the base using z-histograms and aligns the bounding boxes of partial yz-projections. Experimental results with crane camera point clouds of a large construction site show that our proposed techniques are fast and accurate, allowing us to estimate the current floor under construction from the aligned clouds and enabling potential slab state analysis. This work contributes a fully automated method of reality capture and monitoring of multi-building construction sites.

**Keywords:** reality capture, multi-building point cloud, building extraction, BIM model, construction site, crane cameras

## 1. INTRODUCTION

The need for automating progress monitoring in construction projects is well-established in light of the waste involved in manually inspecting sites and updating records (Golparvar-Fard et al., 2011). In the past decade, efforts toward automation have benefited from advancements in on-site spatial survey technologies, which provide as-built information in the form of 2D images and 3D point clouds (Yang et al., 2015b; Wang and Kim, 2019), as well as improvements in computer vision techniques for processing this data (Seo et al., 2015; Zhong et al., 2019). An effective method for extracting useful information from as-built point clouds is to align them with the as-designed BIM model (Bosché, 2010). This method has opened up a plethora of applications in construction,

such as construction progress tracking, safety management and dimensional quality management (Wang and Kim, 2019).

In essence, the problem of aligning as-built and as-designed models is that of point cloud registration, a well-studied topic in Computer Vision (Pomerleau et al., 2015). When applied to the context of the built environment, point cloud registration becomes complex due to the many occlusions, self-similarities and non-model points, which make automation of this pipeline very challenging (Bueno et al., 2018). Several solutions have been proposed for achieving fast and accurate alignment in the construction context (Wang and Kim, 2019), but they need to be updated in the face of changing trends in reality capture of construction.

A recent development is the emergence of multi-building point clouds, made possible by the integration of crane or drone-mounted cameras and photogrammetric techniques. The multi-building scenario presents the problem of isolating the buildings from a noisy construction site point cloud to enable effective alignment with the as-designed Building Information Model (BIM). An initial coarse alignment can be achieved by converting the as-built point cloud into the coordinate system of the as-designed BIM. Further alignment can be achieved by studying point (Kim et al., 2013c) or plane correspondences (Bueno et al., 2018) between the point clouds to be registered, although the latter is more natural for the built environment. Finally, fine alignment can be achieved by the Iterative Closest Point (ICP) algorithm (Besl and McKay, 1992) and its variants (Yang et al., 2015a). For all these registration approaches, removal of outliers is necessary to ensure fast and accurate results. In the case of multi-building point clouds, the outlier ratio is especially large. An efficient method to remove non-building noise is therefore highly desirable.

Another issue that can arise with multi-building point clouds that do not have complete coverage of the entire site is a significant disparity in the quality of different buildings. Buildings that are only partially captured and therefore fragmented can be an obstacle to accurate registration. Also, once a building is extracted from the multi-building point cloud, its base must be identified to accurately delineate the profile of the building.

To address these issues, we present the following solutions. First, we propose a BIM-based 3D bounding box filter, which we call a *building-pass filter*, to remove non-building noise. The filter defines a region of interest based on the outer limits of the BIM model and applies an efficient kd-tree-based search for building points. Such a filter has been used before as a preprocessing step (Han et al., 2018), but we use it additionally as an interim step during alignment and as a postprocessing step. To address the disparity in data quality across buildings, we present an approach to define a *pivot* building from which we obtain the required transformation for the entire multi-building point cloud. We also present a strategy using z-histograms to identify the base of buildings and infer the floor number from the aligned as-built point cloud. We call this algorithm BEAM (BIM-based Extraction and Alignment for Multi-building Point Clouds). The performance of the algorithm is evaluated by comparing it with manually generated ground truth transformations and

examining the proportion of the cast-in-place roof slab that can be correctly extracted after alignment.

Additionally, this is one of few works that study crane camera point clouds. In a previous study (Masood et al., 2019), we tested a building extraction strategy on crane camera point clouds that did not make use of the as-designed BIM, in light of some point clouds in our dataset that were not georeferenced and could thus not easily be aligned with the model. However, georeferencing as-built data based on site referencing systems is a common practice in the industry (Wang and Kim, 2019) and is thus considered necessary for this work. Crane camera technology offers some key advantages over its counterparts like Light Detection And Ranging (LiDAR) and Unmanned Aerial Vehicles (UAVs), such as being fully automated, low-cost, and low-labor (Tuttas et al., 2016). The 3D point clouds obtained from crane cameras can allow daily and automatic inference of the current floor under construction, while 2D images can be used to infer the state of cast-in-place concrete roof slabs.

This paper is organized as follows: section 2 discusses related work; section 3 describes the crane camera dataset; section 4 explains the BEAM algorithm; section 5 presents the results and discussion, including a potential application of mapping the output of BEAM to 2D crane camera images; section 6 discusses some limitations of this work; and section 7 presents the conclusions.

## 2. RELATED WORK

In this section, we study previous works on the following three central themes of our paper: (i) Crane camera point clouds; (ii) Fully automated alignment of as-built data with as-designed BIM data; and (iii) Building extraction in the presence of noise.

### 2.1. Crane Camera Point Clouds

In a comprehensive review of point cloud data acquisition techniques, Wang et al. (2019) identified Light Detection And Ranging (LiDAR) and photogrammetry (including videogrammetry) as the main methods of acquiring point clouds for construction applications. Typically, 3D data in construction has been captured using LiDAR, which provides high-precision point clouds and has been the technology of choice in some important past works (Bosché, 2010; Kim et al., 2013b; Zhang and Arditi, 2013; Bosché et al., 2015). However, laser scanners are expensive and require expert labor, which makes them unsuitable for continuous progress monitoring (Rebolj et al., 2017). Large areas are surveyed using Airborne LiDAR, which involves the significant expense of a piloted airplane carrying specialist laser scanning equipment (Johnson et al., 2014). In addition, Airborne LiDAR produces a distant view of the site that is not suited for close-range analysis.

According to Wang et al. (2019), photogrammetry has gained the most popularity due to the ease of access to the required equipment and the maturity of software packages. Photogrammetric point clouds are obtained from photographic images. Some past works used fixed on-site cameras (Golparvar-Fard et al., 2011; Kim et al., 2013a; Omar et al., 2018) for image capture, but focused only on a small segment of the construction

site. A large number of devices would be required to achieve complete coverage of the construction site, since each visible point needs to be covered by at least two cameras (Braun et al., 2015). Attaching cameras to UAVs is becoming popular (Ham et al., 2016) and results in high coverage of the construction site. But UAVs have certain disadvantages. Aside from the need for flight permissions (Cardot, 2017), there are restrictions such as a security distance to be maintained from buildings and cranes, and maximal flight heights, which can pose a problem for tall buildings (Tuttas et al., 2016). Also, UAVs can only operate in the active area of construction when the cranes do not move, such as during breaks. Additionally, the risk of collisions, image quality deterioration due to bad weather and the difficulties in camera pose estimation with the continuous position changes of the UAV are inhibiting factors (Bang et al., 2017).

Wang and Kim (2019) conducted a comprehensive review of the application of point cloud data in the construction industry. It is evident that crane camera point clouds have received little attention. We review the exceptions subsequently. Tuttas et al. (2016) were the first to study as-built point clouds generated from crane cameras. They did a comparative analysis of image acquisition from crane cameras with hand-held cameras and UAVs. Based on their experiments, the authors suggested that despite the effort required to mount the camera and limited flexibility due to the limited range of motion of cranes, crane cameras are the best technique in terms of automation, safety and effort required. Xu et al. (2018) presented a method to detect and reconstruct scaffolding components from point clouds. They proposed a 3D local feature descriptor to extract features that were used to train a machine learning classifier to identify points belonging to linear straight objects. Despite good results on noisy crane camera point clouds, the authors suggested that outlier removal prior to applying the descriptor could improve the performance.

Braun et al. (2015) presented a method to detect built elements in an as-built crane camera point cloud. They used two cameras mounted on the boom of a crane to acquire images. The authors proposed to establish the sequence of construction of elements in the form of a “precedence relationship” graph. This was meant to track the built status of occluded elements, which could be inferred from the graph since it could not from the point cloud. However, such element-wise analysis requires the registration of the point cloud with the BIM model, which they ensured by manually inserting control points. The registration is therefore not fully automatic. In the next section, we review key past works that deal with fully automated point cloud registration in the construction context.

## 2.2. Registration of As-Built and As-Designed Models

Following the typical point cloud registration pipeline, as-built and as-designed point clouds can be aligned by preprocessing to remove noise, coarse registration to achieve a rough alignment and fine registration to achieve near-optimal alignment. Preprocessing is discussed in section 2.3. As for coarse registration, some important early works proposed

plane-matching (Bosché, 2012) and Principal Component Analysis (PCA)-based alignment (Kim et al., 2013b), but a recent review paper identifies the work of Bueno et al. (2018) as the state-of-the-art in the construction context. The approach in this work is to find matching sets of plane patches (and not just planes as in Bosché, 2012) in the as-built and as-designed data, find a set of transformations between these patches and then shortlist the best transformation through a series of support-assessment stages. The plane-based registration framework presented in this work is a robust approach that fits naturally to the built environment and was shown to successfully register different kinds of buildings. However, in cases when the geometry of the building is simple, some assumptions can be made which obviate the need for extracting planes and assessing support. Instead of searching for matching planes in the entire point cloud and assessing a large set of transformations, we can simply align the 2D projections of the top and facade of the buildings. In Wang et al. (2016), the problem of 3D transformation was converted to the simpler 2D case by aligning 2D projections. We take a similar approach in this work, except that instead of obtaining the 2D projection from a fitted plane, we obtain it by directly projecting the as-built point cloud. Additionally, we project only part of the as-built point cloud to ensure that noise at the base does not interfere with the alignment. Also, aside from alignment, we require filtering of fine noise and base identification, which we achieve by strategic application of a BIM-based filter and z-histograms, respectively.

For fine registration, the ICP algorithm is the standard approach (Bosché, 2010; Kim et al., 2013b; Bueno et al., 2018). However, the ICP algorithm requires point matching, which involves the assessment of all as-built data points. This can create a significant computational overhead when dealing with multi-building point clouds that contain a large amount of noise. Bosché (2010) suggested that some form of point sampling should be used to reduce the computational cost of ICP. Our proposed BIM-based filter removes non-building points efficiently and thus removes the need for analyzing the entire as-built point cloud. A recent work presents a method to speed up ICP by removing ground points from laser-scanned data for robot navigation (Li et al., 2019). Aside from the different data-type and application, our work differs from ground point extraction in the sense that we need to remove all non-building points, regardless of their being ground or non-ground points. This requirement of ours can be classed as *building extraction*, which we review in the next section.

When an as-designed model is not present, or the disparity between the as-designed and as-built data is large (such as in early phases of construction), as-built data separated temporally can be matched by finding feature correspondences across 2D images (Tuttas et al., 2017). However, we do not explore as-built vs as-built registration in this work.

## 2.3. Building Extraction for Construction Sites

The problem of building extraction is to identify and segment buildings from visual data of a scene. Building extraction



techniques have largely been developed for distant aerial imagery for urban planning and monitoring applications (Tomljenovic et al., 2015; Boonpook et al., 2020). Building extraction can either be data-driven (Nguyen et al., 2020) or model-driven (Zheng and Weng, 2015). Data-driven methods are the natural choice when a suitable model is not present. A previous work of ours (Masood et al., 2019) proposed a building extraction strategy based on 3D convex hull volumes of clusters on an as-built point cloud, based on the observation that buildings are larger than non-building elements. This work did not depend either on the BIM model or the georeferencing of the point cloud to identify buildings. However, the algorithm could suffer in the early stages of construction when non-building elements may be more voluminous than the building area.

When a suitable model is present, model-driven building extraction is more robust (Li et al., 2020). For example, Karantzalos and Paragios (2008) proposed a set of building templates as shape priors to guide the segmentation of buildings from aerial imagery, achieving superior results to pure intensity-based segmentation. In the construction context, BIM models are now ubiquitous and can be naturally used as strong geometric and semantic priors for building extraction from multi-building construction scenes. For example, Han et al. (2018) used the minimum and maximum values of the BIM model to filter a large UAV point cloud, leading to an 80% reduction in the number of points. They included a threshold to account for registration errors. In this work, we build on the idea of BIM-based filtering by defining a 3D bounding box filter based on the BIM model. In addition to global filtering to extract buildings, we show how in combination with z-histograms of the building, such a BIM-based filter can aid in base identification and as a postprocessing step after alignment. A recent work (Huang et al., 2020) uses the 1D histogram of the horizontal projection of a building point cloud to reason in the frequency domain about vertical translation. We instead use the z-histogram to identify the base of the building based on the intuition that the base has a greater point count than the noisy regions.

### 3. DATA DESCRIPTION

The data was collected on the site of the Tripla project located in Helsinki, Finland, which includes a shopping center, hotel, housing and offices. The total area of the site is 183,000 floor  $m^2$ . A crane camera solution developed by Pix4D was used to collect data (Cardot, 2017). Two independent cameras were mounted on the jib of a tower crane. The cameras were located approximately 13 and 37 m from the rotation axis of the crane, respectively and their viewing direction was toward the ground. The vertical height of the crane boom, and thus of the cameras, was about 100 m from sea level. Since the cameras were in nadir orientation, the viewing directions of the camera did not change when the crane moved. The focal length per detector width was approximately 28 mm for 35 mm film. Images were automatically taken as the crane would begin operation and then transferred to the Pix4D Cloud, where they were converted to 2D maps and 3D point clouds. Points were calculated with the stereo baseline across the

**TABLE 1** | Description of as-built point cloud dataset.

Point cloud #	Date (dd/mm/yyyy)	Density (points/ $m^3$ )	Number of points
1	17/08/2018	949.4	17,349,826
2	20/08/2018	988.4	15,117,822
3	1/10/2018	1110.43	16,499,213
4	1/11/2018	1338.91	15,909,536
5	5/11/2018	1032.46	14,144,080
6	7/11/2018	756.85	16,4806,06
7	13/11/2018	881.31	10,915,918
8	19/11/2018	885.19	13,100,825

crane jib and the overlap in the turning direction was at least 60%. The size of the images was  $3648 \times 5472$  pixels. The entire process, from image capture to daily point cloud, was automatic. From a point cloud dataset spanning August to November 2018, eight point clouds were selected based on their being successfully georeferenced and also containing at least some segment of all three buildings on the site. The georeferencing was performed automatically using Global Positioning System (GPS) values. The dates, densities and point counts of the point clouds are shown in **Table 1**.

**Figure 1A** shows the as-designed BIM model of the buildings with their respective labels, while **Figure 1B** shows the corresponding labels on an as-built point cloud.


The point clouds are too fragmented for element-wise identification, but the geometry of the facade is retained to a reasonable degree. This can be used for estimating the number of the current floor under construction. The point cloud contains a large amount of non-building noise, which presents two problems: (i) it can interfere with the alignment with the BIM model and (ii) there would a large computational overhead for analyzing the entire point cloud. Also, the base contains multiple occlusions which can interfere with identifying the boundaries of the building. Additionally, while none of the buildings is fully captured, buildings B and C are relatively more fragmented.

In order to achieve good alignment, the non-building noise must be eliminated. Following this, the best-captured building can be used to obtain the necessary transformations for alignment. Then, the base of the buildings (which may be occluded) must be identified. Finally, the building point clouds must be aligned with the BIM model. Once this is achieved, the current floor under construction can be inferred from the aligned cloud. In the next section, we present our method of achieving these objectives in light of these requirements.

## 4. BEAM: BUILDING EXTRACTION AND ALIGNMENT FOR MULTI-BUILDING POINT CLOUDS

### 4.1. Overview

In this section, we present BEAM, which is our solution to address the problems outlined in section 3. An initial coarse alignment is achieved by conversion of the global coordinate



system (in which the as-built point clouds are originally defined) to the local coordinate system (of the BIM model) followed by correction of the zero-point offset and angular offset, which we easily obtain from design information. To address the problem of non-building noise, we apply the building pass filter to remove the coarse non-building noise, leaving only some noise around the building profiles. Then, for further coarse alignment, fine noise removal and base detection, we select the best-captured building as the *pivot* building and apply the following steps. We align the xy projections (using ICP), apply the building-pass filter to remove some fine noise, identify the base of the buildings using z-histograms, align the yz projections using bounding box alignment and apply the building-pass filter again for further fine noise removal. We then apply the 2D transformations obtained for the pivot building to the other buildings, along with the same strategic application of the building-pass filter and base alignment. The result is a well-filtered and BIM-aligned as-built point cloud, from which we infer the current floor under construction. The algorithm is illustrated in **Figure 2** and explained subsequently.

Let a construction site point cloud from the dataset (of eight point clouds) be  $\mathcal{P} = \{p_1, \dots, p_N\}$ ,  $\mathcal{P} \subset \mathbb{R}^3$  with  $p_i = (p_x^i, p_y^i, p_z^i)^T \in \mathbb{R}^3$ . for  $i = 1, \dots, N$ . Let  $\mathcal{B}$  be a point cloud

obtained from the as-designed BIM model. Our target is to obtain  $\mathcal{L} = \{\mathcal{L}_A, \mathcal{L}_B, \mathcal{L}_C\}$ , which is the set of point clouds corresponding to buildings A, B, and C, such that  $\mathcal{L}$  is aligned with  $\mathcal{B}$ . The first step is coordinate conversion which is explained below.

## 4.2. Coordinate Conversion

The location data in the as-built point clouds is in terms of global coordinates defined by the Universal Transvers Mercator (UTM) system for zone 35 V, also known as ETRS-TM35FIN (Uikkanen, n.d.). UTM coordinates consist of easting and northing values ( $E, N$ ). The BIM model is defined in terms of local ( $X, Y, Z$ ) coordinates. The axes of the local coordinate system are selected so as to follow nearby streets and outer-wall directions of buildings. The zero point for the BIM model is set to be in the South-West direction from the site area, thus giving positive  $X$  and  $Y$  coordinate values for all locations on the site. Let's refer to this zero point, expressed in UTM coordinates, as ( $E_0, N_0$ ). The height value  $Z$  is the same for both local and global coordinates and it follows the N2000 coordinate system, which expresses the height from the theoretical sea level mean height. Local  $X$  and  $Y$  coordinate axes differ by  $\theta = 11.4^\circ$  from the global  $E$  and  $N$  axes, as is illustrated in **Figure 3**. Both the global zero point and angular offset were obtained at the start of the project (from the architect and site drawing, respectively), after which we were able to apply the conversion to all point clouds without any manual intervention.

In order to convert the point cloud into local coordinates, we shift the as-built point cloud by the local zero and rotate by  $\theta$ , as is expressed in the following equation:


$$\begin{bmatrix} X \\ Y \end{bmatrix} = \begin{bmatrix} \cos\theta & \sin\theta \\ -\sin\theta & \cos\theta \end{bmatrix} \times \begin{bmatrix} E - E_0 \\ N - N_0 \end{bmatrix} \quad (1)$$

We will refer to the converted point cloud as  $\mathcal{P}_{local}$ . The results of conversion for Point Cloud 1 are shown in **Figure 4**. As can be seen from the figure, the conversion leads to a rough alignment of the point cloud with the BIM model.

## 4.3. Building-Pass Filtering

The *building-pass filter* is a 3D bounding box filter (Rusu and Cousins, 2011) whose parameters are defined using the BIM model to specify a region of interest that contains the buildings. The data points that fall within the region of interest are searched using a  $k$ -d-tree, a modern formulation of which is given in Skrodzki (2019). We define the building-pass filter subsequently. Let the limits of  $\mathcal{B}$  be  $limits_{\mathcal{B}} = \{x_{min}^{\mathcal{B}}, x_{max}^{\mathcal{B}}, y_{min}^{\mathcal{B}}, y_{max}^{\mathcal{B}}, z_{min}^{\mathcal{B}}, z_{max}^{\mathcal{B}}\}$ . The filter is a cuboid whose vertices are defined by  $limits_{\mathcal{B}}$  as shown below:

$$bpf = \begin{bmatrix} x_{min}^{\mathcal{B}} & y_{min}^{\mathcal{B}} & z_{min}^{\mathcal{B}} \\ x_{max}^{\mathcal{B}} & y_{min}^{\mathcal{B}} & z_{min}^{\mathcal{B}} \\ x_{min}^{\mathcal{B}} & y_{max}^{\mathcal{B}} & z_{min}^{\mathcal{B}} \\ x_{max}^{\mathcal{B}} & y_{max}^{\mathcal{B}} & z_{min}^{\mathcal{B}} \\ x_{min}^{\mathcal{B}} & y_{min}^{\mathcal{B}} & z_{max}^{\mathcal{B}} \\ x_{max}^{\mathcal{B}} & y_{min}^{\mathcal{B}} & z_{max}^{\mathcal{B}} \\ x_{min}^{\mathcal{B}} & y_{max}^{\mathcal{B}} & z_{max}^{\mathcal{B}} \\ x_{max}^{\mathcal{B}} & y_{max}^{\mathcal{B}} & z_{max}^{\mathcal{B}} \end{bmatrix} \quad (2)$$



We add a tolerance  $tol$  to  $bpf$  defined as follows:

$$tol = \begin{cases} \delta & \text{if vertex is } max \\ -\delta & \text{if vertex is } min \end{cases} \quad (3)$$

The tolerance is required because the as-built point cloud is misaligned with the as-designed BIM to start with. Once the cuboidal region of interest is created, a 3D  $k$ -d-tree is built to efficiently find the points in  $P_{local}$ , which is explained subsequently. First, we determine the *cutting dimension*  $\bar{d}$ . This is the dimension in which two points  $p_a$  and  $p_b$  exist such

that  $|p_a^{\bar{d}} - p_b^{\bar{d}}| \geq |p_e^{\bar{d}} - p_f^{\bar{d}}|$ , where  $\bar{d}$  refers to the other two dimensions. After this, we sort the values in  $\bar{d}$  (held in a set  $S$ ) and find the median of  $S$ . This median forms the root node of the tree. All values less than the median are assigned to the left child and those greater than the median to the right child. The algorithm then recurses on the children nodes. If the number of points corresponding to a particular node is less than the bucket size  $b$  (which we take as 5,000), we cease to partition the points and instead label the node as a leaf node. Note that we implement a leaf-based tree in which all the points are stored at the leaf nodes (and not at the inner nodes as in the case of non-leaf based trees).

This considerably decreases the space required to store the tree (Behley et al., 2015). The computational complexity of building the kdtree is typically  $O(N \log N)$ .

Once the kdtree is built, we can now efficiently search for points within the building-pass filter. The *cutting threshold*  $\alpha_{node}$ , is defined as follows:

$$\alpha_{node} = \frac{S_{\frac{N_S}{2}} + S_{\frac{N_S}{2}+1}}{2} \quad (4)$$


where *node* is the index of the current nodes in the kdtree and  $N_S$  is the number of points in  $S$ . Equation (4) is the median of the elements of  $S$  when  $N_S$  is even. If  $N_S$  is odd, it is rounded to the

nearest greater integer. Starting the tree traversal from the root node, if the maximum building-pass filter limits corresponding to the cutting dimension at the node exceed (or are equal to)  $\alpha_{node}$ , we move to the right child of the current node. Then, if the minimum building-pass filter limits are less than (or equal to)  $\alpha_{node}$ , we move to the left child of the current node. This continues until a leaf node is found. Now, the points in the leaf node are assessed for presence within the building-pass filter, after which the algorithm moves back up the tree to the next untested node. All leaf nodes that are of a lower index than the last visited leaf node cannot possibly contain the desired points and are thus eliminated from the search. For our dataset, for a bucket size of 5,000, the kdtree reduces the search space by 72% on average compared to a brute force search.


We apply the building-pass filter to  $\mathcal{P}_{local}$  with  $tol = 5$  m to accommodate the initial misalignment. The results will be shown in section 5. With most of the non-building portion of  $\mathcal{P}_{local}$  removed, we achieve the set  $\mathcal{U} = \{\mathcal{U}_A, \mathcal{U}_B, \mathcal{U}_C\}$  of unaligned building point clouds. To aid building-specific analysis, we define the corresponding set  $\bar{\mathcal{B}} = \{\mathcal{B}_A, \mathcal{B}_B, \mathcal{B}_C\}$  of as-designed point clouds obtained from the BIM model.

#### 4.4. Alignment of the Pivot Building and Base Detection

We select  $\mathcal{U}_A$  as the pivot building since it has the best coverage, find the required transformation for it and then apply the resulting transformations to  $\mathcal{U}_B$  and  $\mathcal{U}_C$ . Since the outer geometry



**FIGURE 3 |** Angular deviation of X and Y axes of local coordinate system (of the BIM model) from the UTM35V global coordinate system (E, N).



**FIGURE 4 |** As-built Point Cloud 1 after coordinate conversion seen against the as-designed BIM model.



of the building is simple, we can convert the 3D alignment to 2D by considering the 2D projections of the top and facade of the building. We first align the  $xy$  projections of the point clouds, after which we identify the base of the as-built point cloud, following which we align the  $yz$  projections of the point clouds. These steps are detailed subsequently.

#### 4.4.1. Alignment of $xy$ Projections

We find the transformation  $T_{xy}$  that aligns the  $xy$  projections of  $\mathcal{U}_A$  and  $\mathcal{B}_A$  using the standard point-to-point ICP algorithm. In order to prevent base noise from interfering with the alignment, we only project the top 50% of  $\mathcal{U}_A$ . We then apply  $T_{xy}$  to  $\mathcal{U}_A$  to achieve an  $xy$ -aligned 3D as-built point cloud, to which we apply the building-pass filter to remove fine noise around the building profile. This time, we wish to filter only above the building and to its sides and wish to retain the base area for analysis in the next step. Thus, we set the minimum  $x$  and  $z$ -limits to  $-\infty$  and the maximum  $x$ -limit to  $\infty$ . All other limits remain as in Equation (2). Also, we can now set  $tol$  to zero since the point cloud is already  $xy$ -aligned. We denote the  $xy$ -aligned point cloud as  $\mathcal{U}_A^{xy}$ .


#### 4.4.2. Base Identification

Identifying the base of the building is a challenging task because of a concentration of construction noise at the base. Our strategy to identify the base is to study the histogram of the  $z$ -values at the base of the building and select the mode of these values, based on the intuition that the base of the building has a far greater point count than the noisy regions. We first take the  $yz$  projection of  $\mathcal{U}_A^{xy}$ , downsample it with a grid filter and define the region of interest to be the bottom 20% portion of the building. We then construct the histogram with a bin width of 0.1 m and take the mode as the base height. For safety, we add a small tolerance of 0.1 m, which is effectively the histogram bin next to the mode bin. The histogram for Point Cloud 1 is shown in **Figure 5**. The peak corresponds to 31.9 m and thus 32 m is taken as the base height. Once the height is estimated, we can simply remove the points below base. The resulting point cloud is denoted as  $\mathcal{U}_A^g$ .

#### 4.4.3. Alignment of $yz$ Projections

To perform the  $yz$ -alignment of  $\mathcal{U}_A^g$  and  $\mathcal{B}_A$ , we simply align their respective bounding boxes. However, if the  $y$  limits of the base extend beyond those of the overall  $y$ -limits of the building, the bounding box may become enlarged beyond the envelope of the building. In order to prevent this from distorting the  $y$ -alignment, we take the bounding box of the top 90% of the building. Then, we simply shift the bounding box by the difference between the bounding box edges which are normal to the  $y$ -axis. To perform  $z$ -alignment, we take the bounding box of the entire  $yz$  projection and shift it by the difference between the bounding box edges which are normal to the  $z$ -axis.

Once the  $yz$ -alignment is complete, we apply the building-pass filter again as defined in Equation (2) and with  $tol$  set to zero. Finally, we achieve the set of aligned building point clouds  $\mathcal{L} = \{\mathcal{L}_A, \mathcal{L}_B, \mathcal{L}_C\}$ .



**FIGURE 5** | Histograms of  $z$ -values for the bottom 20% portion of building A for Point Cloud 1. The red bar corresponds to the mode bin and the green bar is the selected base height.

### 4.5. Floor Level Estimation

In this section, we explain our strategy to estimate the current floor under construction. We first study the histogram of  $z$ -values between the ends of the  $yz$  projections of the building sections and select the largest  $z$  value (i.e., the largest height) as the height of the section. To ensure that our selected region of interest falls within the ends of the building section, we shrink the region of interest by 10% on each side. Also, to avoid selecting a  $z$  value corresponding to an outlier, we set a simple noise criterion as follows:

$$\frac{n_i}{n_{total}} > \gamma \quad (5)$$

where  $n_i$  is the number of points at the  $i^{th}$  bin of the histogram,  $n_{total}$  is the total number of points in the region of interest and  $\gamma$  is a noise threshold which we set to 0.005.

Once the height of each slab section is obtained, we use a rule base created from design heights to infer the floor number. Specifically, we check if the estimated floor height falls between the upper levels (according to the design) of the roof slabs of the previous and current floor. The rule base is shown in **Table 2**. We add a tolerance  $t_h$  of 1 m, considering that the floor height is 3.1 m. The results are presented in section 5.

## 5. RESULTS AND DISCUSSION

In this section, we discuss the results obtained by applying BEAM to our dataset of eight point clouds, following which we. To avoid congested illustrations, only point clouds 1 and 5 are illustrated.

### 5.1. Building-Pass Filter

**Figure 6** illustrates the application of the building-pass filter to point clouds 1 and 5. The filter removes most of the non-building



portion of the construction site. The misalignment is relatively less for Point Cloud 1 and thus the need for the tolerance may not be obvious. However, Point Cloud 5 is noticeably more misaligned, as is evident from the figure. Without a tolerance, the

filter would remove some portion of the building. The filter leads to an average point count reduction of 63.32%.

**TABLE 2 |** Rule base used to infer floor number.

Height range	Floor #
$(33+t_h, 37.2+t_h]$	1
$(37.2+t_h, 40.3+t_h]$	2
$(40.3+t_h, 43.4+t_h]$	3
$(43.4+t_h, 46.5+t_h]$	4
$(46.5+t_h, 49.6+t_h]$	5
$(49.6+t_h, 52.7+t_h]$	6
$(52.7+t_h, 55.8+t_h]$	7
$(55.8+t_h, 58.9+t_h]$	8
$(58.9+t_h, 62+t_h]$	9
$(62+t_h, 65.1+t_h]$	10
$(65.1+t_h, 68.03+t_h]$	11
$>68.03+t_h$	12

*The heights correspond to upper roof slab levels of each floor taken from the as-designed BIM model.*


## 5.2. Alignment and Base Detection

**Figure 7** shows the xy-alignment for point clouds 1 and 5. The ICP algorithm corrects the angular orientation of both point clouds reasonably well. The results are similar for the entire dataset. **Figure 8** shows the results for base detection for both point clouds. The base is identified correctly in both cases and the results are consistent across the entire dataset. Next, **Figure 9** shows the yz-alignment for both point clouds. Point Cloud 5 is significantly misaligned in both  $y$  and  $z$  directions, but this is corrected effectively by the algorithm.

## 5.3. Registration Accuracy and Speed

The following metrics were used to evaluate the registration accuracy and speed of the proposed algorithm:

- The difference between the transformations obtained from the proposed algorithm and the ground truth transformations, which were obtained by manually applying a rotation and translation to each aligned point cloud such that the cast-in-place slab of section 1 (see **Figure 10**) was finely aligned with the corresponding slab in the BIM model. The rotation (angular correction) was applied such that the slabs



**FIGURE 6 |** First application of the building-pass filter (with tolerance 5) to **(A)** Point Cloud 1 and **(B)** Point Cloud 5.




FIGURE 7 | Alignment of xy projections using ICP for (A) Point Cloud 1 and (B) Point Cloud 5.

boundaries became parallel as judged by visual inspection. Then, translation was applied such that the bottom-right corners of the slabs (when viewed overhead) coincided. We report the angular and translation errors  $\delta_R$  and  $\delta_T$ , respectively, as defined below:

$$\delta_R = |\alpha_{gtruth} - \alpha_{BEAM}| \quad (6)$$


$$\delta_T = \|T_{gtruth} - T_{BEAM}\| \quad (7)$$

where  $T = [t_x, t_y, 0]$ . The accuracy of z-alignment is assessed in terms of the floor estimation, as discussed in section 4.

- Root-Mean-Square Error (RMSE), which is the Euclidean distance (in meters) between the aligned point clouds.
- Computation time (in seconds) to run BEAM on an Intel Core i7-9750HF CPU with 16 GB RAM in MATLAB-R2020a software.

The results are shown in Table 3. The mean angular error is 1.34 degrees, translation error is 2.6 m and RMSE is 0.7 m. These errors are small enough to enable further analysis of the slab states, as will be discussed in section 5.5. Considering the large average number of points in our dataset (14,940,000), the mean computation time of 159.86 s is small.





## 5.4. Floor Estimation

The floor estimation was limited to building A, because only this building is consistently captured across its entire width. But since this building is not captured across its entire length, the floor level could be calculated for two out of four sections of the building, as is illustrated in **Figure 10**.

The ground truth of the current floor under construction was obtained from the Pix4D cloud by manual inspection. The results of the floor estimation are shown in **Table 4**. The current floor is estimated accurately for every point cloud, except for point cloud 4, where the actual floors “12” and “11” are estimated as “11” and “9,” respectively. As shown in **Table 5**, the estimated heights for sections 1 and 2 corresponding to Point Cloud 4 are 67.9 and 62.8 m, respectively, while floor 12 is detected beyond 69.03 m and floor 11 beyond 63 m. The reason for the misestimation is the small difference in scale between the BIM point cloud and the as-built point cloud, the latter being smaller.

## 5.5. A Potential Application of Crane Camera Images: Slab State Recognition

Crane camera data could be used to enable remote monitoring of construction sites and automatic alerts in construction

workflow when progress falls behind expectations, especially to aid those construction managers who are off-site and whose workflows require real-time knowledge of any deviations of plans. For example, automatic inference of the current floor under construction from BIM-aligned point clouds, as was demonstrated in this work, could keep managers informed of deviations from the schedule.

Another potential application is that once the current floor under construction is known, cast-in-place concrete roof slabs can be extracted. As we shall demonstrate subsequently, the slabs can be accurately extracted from the aligned as-built point cloud. We can measure the overlap between the slabs in the BIM model and those in the as-built point cloud using Intersection Over Union (*Iou*) (Csurka et al., 2013). For a reference area *R* and estimated area *E*, the *Iou* can be defined as:

$$IoU = \frac{E \cap R}{E \cup R} \quad (8)$$

To obtain the estimated slab areas, we manually determined the slab corners of sections 1 and 2 (see **Figure 10**) from the set of aligned clouds  $\mathcal{L}_A$ . The reference slab areas were obtained from the BIM model. An average *Iou* of 0.833 was obtained. This is a good overlap that can be leveraged to infer the state of the slab. For example, Bang and Kim (2020) considered bounding boxes with *Iou* more than 0.80 to represent the same construction scene, therefore such bounding boxes were merged together before object recognition was performed.


Once the slab region is identified, we can map the 3D points to the corresponding 2D crane camera images used to create them. From these 2D images, we can infer whether the slab contains no formwork, formwork only, formwork and rebar or completed rebar, as shown in **Figure 11**.

A generalized version of this application was explored by Dimitrov and Golparvar-Fard (Dimitrov and Golparvar-Fard, 2014), who used a bag-of-words model with a Support Vector Machine (SVM) for material recognition from site images. The authors considered 20 classes of materials. To improve the accuracy, they suggested that classes be limited to the material expected in a particular region under construction. Also, the authors suggested the need for identifying a region in a photograph belonging to a single material so that material classification could be restricted to that region. They suggested that these regions could be derived by back-projecting BIM element surfaces or points of a segmented point cloud onto site images. This kind of automated region extraction was explored in Aikala et al. (2019). In future work, we intend to automatically infer the slab state by formulating this as a scene recognition problem.

## 6. LIMITATIONS

Due to incomplete coverage of the construction site by the cameras, the point clouds were fragmented. The most complete portion of the point cloud showed half of the facade of a building albeit a good view of the roof slabs. The rear was completely missing since it was not within the camera's field of view. Only a





**FIGURE 9 |** Alignment of yz projections for **(A)** Point Cloud 1 and **(B)** Point Cloud 5.



small segment of other buildings was available, which precluded them from floor estimation. Future work should consider how more crane cameras can be placed to extend coverage and examine a possible integration with drone images or images from fixed cameras.

In our data, and in fact for most buildings, the yz alignment is a case of matching straight edges, which is achieved by matching their bounding boxes. If the shapes are irregular, aligning the

bounding boxes may not lead to a close alignment. In such cases, edge detection methods such as Sobel (Kittler, 1983) and Canny (Canny, 1986) or their modern variants such as CannySR (Akinlar and Chome, 2015), Predictive Edge Linking (Akinlar and Chome, 2016) and HT-Canny (Song et al., 2017) may be employed to trace the edges and then attempt the alignment.

The as-built point cloud was slightly out of scale with respect to the BIM model, which affected the accuracy of floor estimation.





**TABLE 3 |** Rotation error ( $\delta_R$ ), translation error ( $\delta_T$ ), RMSE, and computation time of BEAM.

Point cloud #	$\delta_R$ (degrees)	$\delta_T$ (m)	RMSE (m)	t (s)
1	0.43	0.89	0.79	150.65
2	0.36	0.4	0.7	136.07
3	1.36	4.08	0.72	187.66
4	1.19	2.22	0.61	163.53
5	2.59	4.79	0.76	156.52
6	2.94	5.64	0.71	171.37
7	0.71	0.72	0.74	150.51
8	1.18	2.04	0.58	162.53
Mean	1.34	2.6	0.7	159.86

**TABLE 4 |** Floor estimation results.

Point cloud #	Actual floor		Estimated floor	
	Section 1	Section 2	Section 1	Section 2
1	8	6	8	6
2	8	6	8	6
3	10	9	10	9
4	12	10	11	9
5	12	10	12	10
6	12	11	12	11
7	12	11	12	11
8	12	11	12	11

Automatically equalizing the scale of the as-built point cloud and BIM model should be addressed in future work.

## 7. CONCLUSION

Reality capture technologies are improving in level of automation and coverage, which is making it possible to acquire images and 3D point clouds of large, multi-building construction sites. In this work, we proposed BEAM, which is an algorithm that addresses some unique computational challenges that arise in the

processing of multi-building point clouds. Firstly, to eliminate coarse and fine non-building noise, we presented a BIM-based building-pass filter. Results with eight point clouds of a three-building construction site showed that the filter offers a robust, flexible, and efficient way to remove both coarse and fine noise, leading to an average point count reduction of 63.32% for our dataset. Additionally, the building-pass filter can easily be applied to multi-building point clouds from other reality capture technologies (such as drones) and is relevant for point clouds of diverse densities. Secondly, in view of the holes in



**TABLE 5 |** Estimated slab heights shown against the rule base created from design heights.

Point cloud #	BIM-based rule base		Estimated height (m)	
	Section 1	Section 2	Section 1	Section 2
1	$(55.8+t_h, 58.9+t_h]$	$(49.6+t_h, 52.7+t_h]$	59.6	53.7
2	$(55.8+t_h, 58.9+t_h]$	$(49.6+t_h, 52.7+t_h]$	58.9	53.2
3	$(62+t_h, 65.1+t_h]$	$(58.9+t_h, 62+t_h]$	64	61.1
4	$>68.03+t_h$	$(62+t_h, 65.1+t_h]$	67.9	62.8
5	$>68.03+t_h$	$(62+t_h, 65.1+t_h]$	69.3	64.4
6	$>68.03+t_h$	$(65.1+t_h, 68.03+t_h]$	71.3	67.3
7	$>68.03+t_h$	$(65.1+t_h, 68.03+t_h]$	70.9	68.1
8	$>68.03+t_h$	$(65.1+t_h, 68.03+t_h]$	71.4	68.7

the data and disparity in data quality across buildings, we proposed an alignment strategy in which the best-captured building is selected as the pivot and partial 2D projections of the building are aligned. The registration accuracy was shown to agree well with ground truth, but could be further improved with fine alignment algorithms. We studied how the achieved alignment could facilitate slab analysis by calculating the slab region that could be extracted based on design dimensions. We achieved a mean IoU of 0.83, which we expect is a sufficiently good overlap for slab state analysis. Thirdly, we proposed a base identification strategy using z-histograms that is iteration-independent and could effectively identify the base for the entire dataset despite occlusions. As a result of successful alignment and base identification, floor numbers could be accurately calculated by mapping the height of the aligned cloud with design heights extracted from the BIM model. One floor was misestimated as a result of the small difference in scale between the as-built point cloud and the BIM model. This should be addressed by automatic scale-matching in future work.

The results of this study contribute to real-time construction progress monitoring by offering a fully automated, computationally feasible and accurate method of aligning daily construction site point clouds with as-designed models. This could facilitate remote management of construction sites, better

organization of support functions such as procurement and logistics, and more accurate reporting of project status at the company or business unit level. Also, this is one of few works that uses crane camera data, which is an emergent technology that offers many benefits in terms of cost and automation compared with other reality capture techniques.

In future work, we intend to explore automatic recognition of the state of cast-in-place slabs by formulating it as a scene recognition problem that can be solved using a Bag-of-Words approach. Also, we intend to address the issues with data quality by installing fixed cameras on the crane and possibly augmenting them with drone data.

## DATA AVAILABILITY STATEMENT

The datasets presented in this article are not readily available because the data belongs to a construction company. Requests to access the datasets should be directed to Mustafa K. Masood, [mustafa.1.khalidmasood@aalto.fi](mailto:mustafa.1.khalidmasood@aalto.fi).

## AUTHOR CONTRIBUTIONS

MM participated in data collection, designed the experiments, developed the methods, analyzed the results, and wrote the manuscript. AA participated in data collection, developed the coordinate conversion method, and contributed ideas to the other methods and gave critical feedback. OS specified requirements and gave critical feedback. VS gave critical feedback. All authors helped shape the research, analysis, and manuscript.

## ACKNOWLEDGMENTS

We thank YIT for providing the data for this study. The work was supported by the Reality Capture and Digitalizing Construction Workflows research projects funded by Business Finland, Aalto University and a consortium of companies. The work was partially supported by the Profi3 research programme on Digital technology ecosystems by Academy of Finland.

## REFERENCES

- Aikala, A., Khalid, M., Seppänen, O., and Singh, V. (2019). Crane camera image preparation for automated monitoring of formwork and rebar progress. In *Proceedings of the 36th CIB W78 Conference*.
- Akinlar, C., and Chome, E. (2015). "CannySR: using smart routing of edge drawing to convert canny binary edge maps to edge segments," in *2015 International Symposium on Innovations in Intelligent Systems and Applications (INISTA)* (Madrid: IEEE). doi: 10.1109/INISTA.2015.7276784
- Akinlar, C., and Chome, E. (2016). PEL: a predictive edge linking algorithm. *J. Vis. Commun. Image Represent.* 36, 159–171. doi: 10.1016/j.jvcir.2016.01.017
- Bang, S., and Kim, H. (2020). Context-based information generation for managing UAV-acquired data using image captioning. *Automat. Construct.* 112:103116. doi: 10.1016/j.autcon.2020.103116
- Bang, S., Kim, H., and Kim, H. (2017). UAV-based automatic generation of high-resolution panorama at a construction site with a focus on preprocessing for image stitching. *Automat. Construct.* 84, 70–80. doi: 10.1016/j.autcon.2017.08.031
- Behley, J., Steinhage, V., and Cremers, A. B. (2015). "Efficient radius neighbor search in three-dimensional point clouds," in *2015 IEEE International Conference on Robotics and Automation (ICRA)* (Seattle, WA: IEEE). doi: 10.1109/ICRA.2015.7139702
- Besl, P., and McKay, N. (1992). A method for registration of 3-d shapes. *IEEE Trans. Pattern Anal. Mach. Intell.* 14, 239–256. doi: 10.1109/34.121791
- Boonpook, W., Tan, Y., and Xu, B. (2020). Deep learning-based multi feature semantic segmentation in building extraction from images of UAV photogrammetry. *Int. J. Remote Sens.* 42, 1–19. doi: 10.1080/01431161.2020.1788742
- Bosché, F. (2010). Automated recognition of 3d CAD model objects in laser scans and calculation of as-built dimensions for dimensional compliance control in construction. *Adv. Eng. Inform.* 24, 107–118. doi: 10.1016/j.aei.2009.08.006
- Bosché, F. (2012). Plane-based registration of construction laser scans with 3D/4D building models. *Adv. Eng. Inform.* 26, 90–102. doi: 10.1016/j.aei.2011.08.009

- Bosché, F., Ahmed, M., Turkan, Y., Haas, C. T., and Haas, R. (2015). The value of integrating scan-to-BIM and scan-vs-BIM techniques for construction monitoring using laser scanning and BIM: the case of cylindrical MEP components. *Automat. Construct.* 49, 201–213. doi: 10.1016/j.autcon.2014.05.014
- Braun, A., Tuttas, S., Borrmann, A., and Stilla, U. (2015). “Automated progress monitoring based on photogrammetric point clouds and precedence relationship graphs,” in *Proceedings of the 32nd International Symposium on Automation and Robotics in Construction and Mining (ISARC 2015)* (Oulu: International Association for Automation and Robotics in Construction). doi: 10.22260/ISARC2015/0034
- Bueno, M., Bosché, F., González-Jorge, H., Martínez-Sánchez, J., and Arias, P. (2018). 4-plane congruent sets for automatic registration of As-Is 3d point clouds with 3D BIM models. *Automat. Construct.* 89, 120–134. doi: 10.1016/j.autcon.2018.01.014
- Canny, J. (1986). A computational approach to edge detection. *IEEE Trans. Pattern Anal. Mach. Intell.* 6, 679–698. doi: 10.1109/TPAMI.1986.4767851
- Cardot, S. (2017). Crane Camera Site Surveying. *GIM Int.* 31, 31–33. Available online at: <https://www.gim-international.com/content/article/crane-camera-site-surveying>
- Csurka, G., Larlus, D., Perronnin, F., and Meylan, F. (2013). “What is a good evaluation measure for semantic segmentation?” in *BMVC*, 2013. (Bristol).
- Dimitrov, A., and Golparvar-Fard, M. (2014). Vision-based material recognition for automated monitoring of construction progress and generating building information modeling from unordered site image collections. *Adv. Eng. Inform.* 28, 37–49. doi: 10.1016/j.aei.2013.11.002
- Golparvar-Fard, M., Bohn, J., Teizer, J., Savarese, S., and Peña-Mora, F. (2011). Evaluation of image-based modeling and laser scanning accuracy for emerging automated performance monitoring techniques. *Automat. Construct.* 20, 1143–1155. doi: 10.1016/j.autcon.2011.04.016
- Ham, Y., Han, K. K., Lin, J. J., and Golparvar-Fard, M. (2016). Visual monitoring of civil infrastructure systems via camera-equipped unmanned aerial vehicles (UAVs): a review of related works. *Visual. Eng.* 4:1. doi: 10.1186/s40327-015-0029-z
- Han, K., Degol, J., and Golparvar-Fard, M. (2018). Geometry- and appearance-based reasoning of construction progress monitoring. *J. Construct. Eng. Manage.* 144:04017110. doi: 10.1061/(asce)co.1943-7862.0001428
- Huang, R., Xu, Y., Hoegner, L., and Stilla, U. (2020). Temporal comparison of construction sites using photogrammetric point cloud sequences and robust phase correlation. *Automat. Construct.* 117:103247. doi: 10.1016/j.autcon.2020.103247
- Johnson, K., Nissen, E., Saripalli, S., Arrowsmith, J. R., McGarey, P., Scharer, K., et al. (2014). Rapid mapping of ultrafine fault zone topography with structure from motion. *Geosphere* 10, 969–986. doi: 10.1130/GES01017.1
- Karantzalos, K., and Paragios, N. (2008). Automatic model-based building detection from single panchromatic high resolution images. *ISPRS Arch* 37, 127–132.
- Kim, C., Kim, B., and Kim, H. (2013a). 4d CAD model updating using image processing-based construction progress monitoring. *Automat. Construct.* 35, 44–52. doi: 10.1016/j.autcon.2013.03.005
- Kim, C., Son, H., and Kim, C. (2013b). Automated construction progress measurement using a 4d building information model and 3d data. *Automat. Construct.* 31, 75–82. doi: 10.1016/j.autcon.2012.11.041
- Kim, C., Son, H., and Kim, C. (2013c). Fully automated registration of 3d data to a 3d CAD model for project progress monitoring. *Automat. Construct.* 35, 587–594. doi: 10.1016/j.autcon.2013.01.005
- Kittler, J. (1983). On the accuracy of the sobel edge detector. *Image Vis. Comput.* 1, 37–42. doi: 10.1016/0262-8856(83)90006-9
- Li, P., Wang, R., Wang, Y., and Tao, W. (2020). Evaluation of the ICP algorithm in 3d point cloud registration. *IEEE Access* 8, 68030–68048. doi: 10.1109/ACCESS.2020.2986470
- Li, X., Du, S., Li, G., and Li, H. (2019). Integrate point-cloud segmentation with 3d LiDAR scan-matching for mobile robot localization and mapping. *Sensors* 20:237. doi: 10.3390/s20010237
- Masood, M., Pushkar, A., Seppänen, O., Singh, V., and Aikala, A. (2019). “Vbuilt: Volume-based automatic building extraction for as-built point clouds,” in *ISARC. Proceedings of the International Symposium on Automation and Robotics in Construction* (Banff, AB: IAARC Publications), 1202–1209. doi: 10.22260/ISARC2019/0161
- Nguyen, T. H., Daniel, S., Gueriot, D., Sintès, C., and Le Caillec, J. M. (2020). Super-resolution-based snake model—an unsupervised method for large-scale building extraction using airborne LiDAR data and optical image. *Remote Sens.* 12:1702. doi: 10.3390/rs12111702
- Omar, H., Mahdjoubi, L., and Kheder, G. (2018). Towards an automated photogrammetry-based approach for monitoring and controlling construction site activities. *Comput. Indus.* 98, 172–182. doi: 10.1016/j.compind.2018.03.012
- Pomerleau, F., Colas, F., and Siegwart, R. (2015). A review of point cloud registration algorithms for mobile robotics. *Found. Trends Robot.* 4, 1–104. doi: 10.1561/9781680830255
- Rebolj, D., Pučko, Z., Babič, N. Č., Bizjak, M., and Mongus, D. (2017). Point cloud quality requirements for scan-vs-BIM based automated construction progress monitoring. *Automat. Construct.* 84, 323–334. doi: 10.1016/j.autcon.2017.09.021
- Rusu, R. B., and Cousins, S. (2011). “3d is here: point cloud library (PCL),” in *2011 IEEE International Conference on Robotics and Automation* (Shanghai), 1–4. doi: 10.1109/ICRA.2011.5980567
- Seo, J., Han, S., Lee, S., and Kim, H. (2015). Computer vision techniques for construction safety and health monitoring. *Adv. Eng. Inform.* 29, 239–251. doi: 10.1016/j.aei.2015.02.001
- Skrodzki, M. (2019). *Neighborhood data structures, manifold properties, and processing of point set surfaces* (Ph.D. thesis). Freie Universität, Berlin, Germany.
- Song, R., Zhang, Z., and Liu, H. (2017). Edge connection based canny edge detection algorithm. *Pattern Recogn. Image Anal.* 27, 740–747. doi: 10.1134/S1054661817040162
- Tomljenovic, I., Häfle, B., Tiede, D., and Blaschke, T. (2015). Building extraction from airborne laser scanning data: an analysis of the state of the art. *Remote Sens.* 7, 3826–3862. doi: 10.3390/rs70403826
- Tuttas, S., Braun, A., Borrmann, A., and Stilla, U. (2016). Evaluation of acquisition strategies for image-based construction site monitoring. *ISPRS Int. Arch. Photogramm. Remote Sens. Spatial Inform. Sci.* 41, 733–740. doi: 10.5194/isprs-archives-XLI-B5-733-2016
- Tuttas, S., Braun, A., Borrmann, A., and Stilla, U. (2017). Acquisition and consecutive registration of photogrammetric point clouds for construction progress monitoring using a 4d BIM. *PFG J. Photogramm. Remote Sens. Geoinformat. Sci.* 85, 3–15. doi: 10.1007/s41064-016-0002-z
- Uikkonen, E. (n.d.). *Finnish Horizontal Coordinate Systems*. Available online at: <http://www.kolumbus.fi/eino.uikkonen/geodocsgb/ficoords.htm> (accessed October 31, 2019).
- Wang, Q., and Kim, M.-K. (2019). Applications of 3d point cloud data in the construction industry: a fifteen-year review from 2004 to 2018. *Adv. Eng. Inform.* 39, 306–319. doi: 10.1016/j.aei.2019.02.007
- Wang, Q., Kim, M.-K., Cheng, J. C., and Sohn, H. (2016). Automated quality assessment of precast concrete elements with geometry irregularities using terrestrial laser scanning. *Automat. Construct.* 68, 170–182. doi: 10.1016/j.autcon.2016.03.014
- Wang, Q., Tan, Y., and Mei, Z. (2019). Computational methods of acquisition and processing of 3d point cloud data for construction applications. *Arch. Comput. Methods Eng.* 27, 479–499. doi: 10.1007/s11831-019-09320-4
- Xu, Y., Tuttas, S., Hoegner, L., and Stilla, U. (2018). Reconstruction of scaffolds from a photogrammetric point cloud of construction sites using a novel 3d local feature descriptor. *Automat. Construct.* 85, 76–95. doi: 10.1016/j.autcon.2017.09.014
- Yang, J., Li, H., Campbell, D., and Jia, Y. (2015a). GO-ICP: a globally optimal solution to 3D ICP point-set registration. *IEEE Trans. Pattern Anal. Mach. Intell.* 38, 2241–2254. doi: 10.1109/TPAMI.2015.2513405
- Yang, J., Park, M.-W., Vela, P. A., and Golparvar-Fard, M. (2015b). Construction performance monitoring via still images, time-lapse photos, and video streams: now, tomorrow, and the future. *Adv. Eng. Inform.* 29, 211–224. doi: 10.1016/j.aei.2015.01.011

- Zhang, C., and Arditi, D. (2013). Automated progress control using laser scanning technology. *Automat. Construct.* 36, 108–116. doi: 10.1016/j.autcon.2013.08.012
- Zheng, Y., and Weng, Q. (2015). Model-driven reconstruction of 3-d buildings using LiDAR data. *IEEE Geosci. Remote Sens. Lett.* 12, 1541–1545. doi: 10.1109/lgrs.2015.2412535
- Zhong, B., Wu, H., Ding, L., Love, P. E., Li, H., Luo, H., et al. (2019). Mapping computer vision research in construction: developments, knowledge gaps and implications for research. *Automat. Construct.* 107:102919. doi: 10.1016/j.autcon.2019.102919

**Conflict of Interest:** The authors declare that the research was conducted in the absence of any commercial or financial relationships that could be construed as a potential conflict of interest.

Copyright © 2020 Masood, Aikala, Seppänen and Singh. This is an open-access article distributed under the terms of the Creative Commons Attribution License (CC BY). The use, distribution or reproduction in other forums is permitted, provided the original author(s) and the copyright owner(s) are credited and that the original publication in this journal is cited, in accordance with accepted academic practice. No use, distribution or reproduction is permitted which does not comply with these terms.